

Deutsche Akkreditierungsstelle

Annex to the Accreditation Certificate D-K-21619-01-00 according to DIN EN ISO/IEC 17025:2018

Valid from: 19.11.2021 Date of issue: 15.09.2022

Holder of accreditation certificate:

qbig GmbH Benzstraße 3, 26789 Leer

The calibration laboratory meets the minimal requirements of DIN EN ISO/IEC 17025:2018 and, if applicable, additional legal and normative requirements, including those in relevant sectoral schemes, in order to carry out the conformity assessment activities listed below.

The management system requirements of DIN EN ISO/IEC 17025 are written in the language relevant to the operations of calibration laboratories and confirm generally with the principles of DIN EN ISO 9001.

Calibrations in the fields:

Mechanical Quantities

- **Fluid quantities**
- Gas flow rate
- Volume of flowing gases

This certificate annex is only valid together with the written accreditation certificate and reflects the status as indicated by the date of issue. The current status of any given scope of accreditation can be found in the directory of accredited bodies maintained by Deutsche Akkreditierungsstelle GmbH at https://www.dakks.de.



Annex to the Accreditation Certificate D-K-21619-01-00

Permanent Laboratory

Calibration and Measurement Capabilities (CMC)

Measurement quantity / Calibration item		Range	9	Measurement quantity / Calibration item	Expanded uncertainty of measurement	Remarks
Fluid quantities Volume flow rate and volume of gases	13 m³/h	to	25 m³/h	Master meter method according to PTB Test Guideline Band 30:2003	0.32 %	Calibration medium: natural gas in operating condition, 8 to 52 bar
	> 25 m³/h	to	40 m³/h		0.30 %	
	> 40 m³/h	to	160 m³/h		0.29 %	
	>160 m³/h	to	400 m³/h		0.28 %	
	>400 m³/h	to	16 000 m³/h		0.27 %	

Abbreviations used:

СМС	Calibration and measurement capabilities
DIN	Deutsches Institut für Normung e.V. (German Institute for Standardisation)
РТВ	Physikalisch-Technische Bundesanstalt (Federal Physical-Technical Institute)